

~~DTIC FILE COPY~~~~DTIC FILE COPY~~

MEMORANDUM REPORT BRL-MR-3815

**BRL**

AD-A224 413

HIGH-RESOLUTION, ITEM-LEVEL WEAPONS MODELING

PAUL H. DEITZ

MARCH 1990

**DTIC**  
ELECTE  
JUL 30 1990  
**S D D**

APPROVED FOR PUBLIC RELEASE; DISTRIBUTION UNLIMITED.

U.S. ARMY LABORATORY COMMAND

BALLISTIC RESEARCH LABORATORY  
ABERDEEN PROVING GROUND, MARYLAND

\*Original contains color  
plates: All DTIC reproductions  
will be in black and  
white\*

80 78 30 313

## DESTRUCTION NOTICE

Destroy this report when it is no longer needed. DO NOT return it to the originator.

Additional copies of this report may be obtained from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Road, Springfield, VA 22161.

The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

The use of trade names or manufacturers' names in this report does not constitute indorsement of any commercial product.



DEPARTMENT OF THE ARMY  
UNITED STATES ARMY LABORATORY COMMAND  
BALLISTIC RESEARCH LABORATORY  
ABERDEEN PROVING GROUND, MARYLAND 21005-5066



REPLY TO  
ATTENTION OF

SLCBBR-DD-S (380a)

20 July 1990

MEMORANDUM FOR Defense Logistics Agency, Defense Technical Information Center, ATTN: DTIC-HAS (Mr. William M. Thompson), Cameron Station, Alexandria, VA 22304-6145

SUBJECT: Technology Screening of Unclassified/Unlimited Reports


1. Reference:

- a. Letter, DTIC-HAS, 21 June 1990, subject as above.
- b. BRL Memorandum Report No. 3815, "High-Resolution, Item-Level Weapons Modeling," March 1990.

2. This Laboratory conducts rigorous technical, security and foreign intelligence reviews of all technical reports which it publishes. Subject area experts and security personnel determined that release of the information found in reference 1b to the general public would not damage the essential secrecy of Army or Department of Defense programs. This determination was based on the reviewers' knowledge of the hostile intelligence threat and the requirements of Department of the Army and US Army Materiel Command regulations. Distribution statement A is appropriate. Request that the Defense Technical Information Center restore the referenced report's original distribution statement.

3. Point of contact is Mr. Douglas J. Kingsley, DSN: 298-6960.

FOR THE DIRECTOR:

  
P. ANN BROWN  
Chief, Security Office

UNCLASSIFIED

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
<small>Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.</small>				
1. AGENCY USE ONLY (Leave blank)	2. REPORT DATE March 1990	3. REPORT TYPE AND DATES COVERED Final		
4. TITLE AND SUBTITLE High-Resolution, Item-Level Weapons Modeling		5. FUNDING NUMBERS		
6. AUTHOR(S) Paul H. Deitz				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)		8. PERFORMING ORGANIZATION REPORT NUMBER		
9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES) US Army Ballistic Research Laboratory ATTN: SLCBR-DD-T Aberdeen Proving Ground, MD 21005-5066		10. SPONSORING / MONITORING AGENCY REPORT NUMBER  BRL-MR-3815		
11. SUPPLEMENTARY NOTES This paper is taken with permission from a series of four articles presented in the Army RD&A Bulletin (published by the U.S. Army Materiel Command, Alexandria, VA 22333-0001), beginning with the MARCH-APRIL and ending with the SEPTEMBER-OCTOBER 1989 issues.				
12a. DISTRIBUTION / AVAILABILITY STATEMENT Approved for Public Release; Distribution Unlimited.		12b. DISTRIBUTION CODE		
13. ABSTRACT (Maximum 200 words) Modern item-level weapons analyses call for a computer environment which supports both geometric modeling and a substantial suite of predictive codes. This paper reviews the generation and interrogation of solid geometric models as well as a diverse set of performance-related applications codes. Examples of geometric modeling of armored fighting vehicles are given, in addition, various structural analysis are illustrated. Such modeling and analytical methods are critical for 1) evaluating the benefits and burdens of design options, 2) supplying necessary Measures-of-Performance for battlefield modeling, and 3) supporting and complementing the field testing of weapons systems				
14. SUBJECT TERMS Geometric Modeling, Weapons Modeling, Vulnerability Analysis, Performance Measures, Item-Level Analysis		15. NUMBER OF PAGES 60		
		16. PRICE CODE		
17. SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED	18. SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED	19. SECURITY CLASSIFICATION OF ABSTRACT UNCLASSIFIED	20. LIMITATION OF ABSTRACT SAR	


NSN 7540-01-280-5500

UNCLASSIFIED

Standard Form 298 (Rev 2-89)  
Prescribed by ANSI Std Z39-18  
298-102

# TABLE OF CONTENTS

	Page
LIST OF ILLUSTRATIONS.....	v
LIST OF TABLES .....	vii
1. INTRODUCTION TO ITEM-LEVEL MODELING.....	1
1.1 How is it Performed?.....	1
1.2 Early Geometric Modeling.....	2
1.3 BRL-CAD Software Tools .....	2
1.4 Examples of Geometry .....	2
1.5 Other CAD Issues.....	3
2. VULNERABILITY/LETHALITY (V/L) OVERVIEW.....	3
2.1 Penetration Performance.....	7
2.2 Framework for Vulnerability Assessment.....	7
2.3 Lumped Parameter Modeling.....	7
2.4 Expected-Value Point Burst Modeling .....	7
2.5 Spare Parts Estimation .....	11
2.6 Stochastic Point-Burst Modeling.....	11
2.7 Summary of Vulnerability Methods .....	14
3. PREDICTIVE SIGNATURES .....	14
3.1 Optical Lighting.....	14
3.2 Infrared Modeling.....	14
3.3 Radar Modeling .....	14
3.4 Summary of Signature Methods.....	21
4. OTHER ITEM-LEVEL ANALYSES .....	21
4.1 Other Application codes .....	21
4.2 Planned BRL-CAD Upgrades.....	21
4.3 Future Issues .....	27
4.4 Summary of Other Application Codes .....	27
DISTRIBUTION LIST .....	29



iii



Availability Co	
Dist	Avail and/ Special
A-1	

INTENTIONALLY LEFT BLANK.

## LIST OF ILLUSTRATIONS

Figure	Page
1. Frontal view of the Bradley Armored Fighting Vehicle built and viewed with the BRL-CAD package. ....	4
2. Rear view of the Bradley. ....	5
3. Transparent rendering of the Bradley Armored Fighting Vehicle. ....	6
4. Concept design for a Mobile Protected Gun System. ....	8
5. Standard cell plot used to display various estimates obtained from vulnerability analyses. ....	10
6. Front-left elevated view of the current Abrams target description with the armor and main armament stripped away. ....	12
7. Simulation of a laser designator on the Bradley vehicle. ....	16
8. Simulation of an overhead smart-munition sensor. ....	17
9. Upper image shows IR field data of Soviet T62 tank. ....	18
10. Two images of an M48 tank which illustrate the synthetic aperture radar (SAR) process. ....	19
11. High-resolution SAR images of an M48 tank. ....	20
12. Comparison of 94 Ghz radar data with simulation for M109 self-propelled howitzer. ....	22
13. High-density shotline sections through a tank target description. ....	23
14. Neutron transport calculations for a concept heavy tank. ....	25
15. Structural calculations for a concept light-armored vehicle. ....	26
16. A sampling of twelve overhead images. ....	28

INTENTIONALLY LEFT BLANK.



## LIST OF TABLES

Table	Page
I. Status of Penetration Data .....	9
II. Status of Behind-Armor Debris (BAD) Data.....	13
III. Models vs Input requirements/preparation times.....	15

INTENTIONALLY LEFT BLANK.

# High-Resolution, Item-Level Weapons Modeling<sup>†</sup>

Dr. Paul H. Deitz

US Army Ballistic Research Laboratory  
ATTN: SLCBR-VL-V (P. Deitz)  
Aberdeen Proving Ground, MD 21005-5000

## ABSTRACT

Modern item-level weapons analyses call for a computer environment which supports both geometric modeling and a substantial suite of predictive codes. This paper reviews the generation and interrogation of solid geometric models as well as a diverse set of performance-related applications codes. Examples of geometric modeling of armored fighting vehicles are given; in addition, various applications codes including vulnerability, signature (optical/IR/MMW), neutron transport, and structural analysis are illustrated. Such modeling and analytical methods are critical for 1) evaluating the benefits and burdens of design options, 2) supplying necessary Measures-of-Performance for battlefield modeling, and 3) supporting and complementing the field testing of weapons systems.

## 1. INTRODUCTION TO ITEM-LEVEL MODELING

Item-level weapons modeling involves the study of a single military system such as a tank, aircraft or communications shelter. The objective of such a study normally involves estimating one or more aspects of item performance in terms of its ability to meet a set of requirements. Typically a military system may fulfill multiple performance requirements so an item may be examined from many aspects. What are typical examples of item-level analysis? They include estimates of weight, size, ability to withstand enemy fire (vulnerability), mobility, detectability (across many wave-length bands), and ability to inflict damage on a particular target class (lethality).

Item-level modeling and assessment are critical to the DoD for a number of reasons. This is the first level of assessment in which a technology can be properly evaluated in terms of actual benefits. For example, a new material for applique armor may appear promising in off-line tests. However only when this armor is applied to a vehicle with due consideration to actual placement and mounting constraints and further subjected to the various threats and attack directions, does a reliable picture emerge as to its true utility. Another example might be the development of a radar coating for the suppression of armored fighting vehicle signatures. A candidate material might show high absorptivity in laboratory tests, however, only when the practical constraints of applying such a

material to the exterior of a vehicle (maintaining access for personnel, weapons, sights, etc.) can the utility of the approach be assessed. So item-level weapons modeling is the first instance where many technologies join with system design and the compromises and tradeoffs become identifiable and quantifiable.

Second, the results of item-level modeling form the basic building blocks from which larger integral assessments are performed. For example, all battlefield modeling whether at the battalion, division, or higher levels is built on probability of kill (PK) assessments of various firer/target matrices. The data for these matrices are all the result of item-level modeling.

Third, item-level modeling supports and extends the utility of actual weapons testing. As is well known, many required field tests are extremely expensive. Item-level modeling assists in weapons assessment by extending the utility of test data for conditions and environments for which tests can't be performed due to constraints of time, costs, or material availability.

### 1.1 How is It Performed?

Item-level modeling can be divided into a two-step process. The first is a Computer-Aided Design (CAD) phase in which a geometric description of the item is

<sup>†</sup> This paper is taken with permission from a series of four articles presented in the Army RD&A Bulletin (published by the U.S. Army Materiel Command, Alexandria, VA 22333-0001), beginning with the MARCH-APRIL and ending with the SEPTEMBER-OCTOBER 1989 issues.

assembled. The result of this is a mathematical file which represents the fully described shapes and materials of which the item is composed. Phase two involves linking the geometric description to an application code to gain understanding about the nature or potential behavior of the item.

The BRL first embarked on this analysis task some twenty years ago to gain insight into two specific forms of weapons performance: survivability/lethality and neutron transport. Whether a particular anti-tank munition will perforate a tank armor is inextricably related to both the characteristics of the munition as well as the system under attack. This includes the details of hit point, armor fall-back angle, line-of-sight projection, material properties, etc. So too the propagation of neutrons from a nuclear event through free space and potentially to occupants of an armored fighting vehicle is a phenomenon driven by the basic physics as applied to the specific geometric and material configuration encountered.

In the remainder of this section, various aspects of the generation of geometry will be discussed. Following sections will review specific applications.

### 1.2 Early Geometric Modeling

In the years following World War II, when the discipline of vulnerability analysis first developed, analysts utilized blue-prints to project bullets through targets. Shotlines were traced manually through a tank or aircraft to catalogue lists of engaged components. Extracted by hand, as well, were points of intersection, surface normals, thicknesses, and materials, clearly a time-consuming process.

Late in the 1960's, the shotline interrogation process was automated to support the first item-level analysis, that of TOW warhead optimization against a tank. To accomplish the first of the two-phase process noted above, a so-called target description was assembled of the target vehicle. To do this, a method of target description preparation called *solid geometric modeling* was developed in which target geometry is described by a family of closed three-dimensional shapes such as cubes, spheres, cones, and the like. The resulting computer input file consisted of the required shapes and defining materials. Upon completion of this input preparation phase, a computer program was invoked which projected rays (or shotlines) through the target description to extract automatically what had formerly been an entirely manual task.

At this point it was possible to compute literally thousands of shotlines on computers which, by today's standards, were modest machines. The bottleneck of building, modifying, and validating target descriptions soon emerged as a substantial problem. Through the 1970's, that process was accomplished entirely by hand, with nothing remotely approximating today's world of interactive graphics. During the initial design process of the XM1 Tank, for example, none of the automated raycasting analyses could be invoked because it was not possible to model geometrically the competitive designs by hand in a timely fashion.

Early in the 1980's, the BRL made a study of the requirements for a suite of CAD tools necessary to support vulnerability and other kinds of item-level modeling. An in-depth review was performed of possible commercial candidates, at the time, none was found capable. An in-house development program was begun which has resulted in an extensive set of CAD programs which are now called BRL-CAD. Although several commercial products in the area of solid geometric modeling have appeared in the market place, none has equaled the Army-developed package in its ability to support the demands of high-resolution item-level weapons modeling.

### 1.3 BRL-CAD Software Tools

BRL-CAD is an extensive suite of Army-generated, supported and owned software specifically designed for the geometric modeling of weapons systems. Consisting of some 200,000 lines of source code and approximately 70 individual programs, the heart of the CAD package is a geometric editor called MGED (for Multiple-device Graphics EDitor). This program, when executed on a suitable computer or engineering workstation, provides the visual feedback and operator control necessary to build, modify, and validate highly complex geometric models of tanks, aircraft, communications vans, etc.

There are many possible mathematical approaches to describing three-dimensional geometry. This is why different modeling schemes are generally incompatible with one another. Originally MGED provided for viewing and editing only the basic shapes mentioned earlier which were part of the first modeling scheme developed in the 1960's. However the BRL-CAD database has been designed to be extensible to new data representations. The database now supports the modeling representations used by Denver Research Institute, a key provider of geometry for the USAF, and a powerful, so-called, spline entity. This latter mathematical form is capable of following complex surface shapes such as those found in cast turrets and aircraft surfaces which are not amenable to modeling via simpler shapes.

Another significant set of tools in BRL-CAD supports raycasting. In addition to supporting vulnerability/lethality analyses, raycasting is also used to simulate neutron trajectories and blast waves, calculate moments-of-inertia, and compute radar cross sections. These utilities are arranged to operate in parallel so as to take maximum advantage of modern computer architectures with multiple-processors (e.g. Cray, Alliant, Convex etc.).

A third set of BRL-CAD utilities supports the generation of images via what are called lighting models. These models simulate what the eye would see from various positions in space. Of note is the fact that there are many other utilities available for manipulating images, performing comparisons, creating labels, etc.

### 1.4 Examples of Geometry

Over the past five years as the new CAD tools have been placed into production at BRL and other sites, many

scores of target descriptions have been created. Illustrative of the high-resolution end of the modeling spectrum are the images shown in Figures 1 to 3. A high-detail version of the Bradley fighting vehicle is shown from the vehicle front-left (Figure 1) and rear-left (Figure 2). The target description used for these images was originally created to support standard vulnerability modeling during the Bradley development cycle. In 1985, the level of internal detail was increased to support the requirements of the Live-Fire testing program. The high level of exterior detail (tracks, hinges, handles) was added later to support high-frequency signature calculations in both the optical and radar bands.

A BRL-CAD lighting model was used to make these images. The model supports multiple sources of light; shadows beneath the main gun can be seen in Figure 1 due to two overhead sources. The amount of specular (shiny) or diffuse (rough-surface) reflections can be adjusted to simulate virtually any material, covering, or illumination condition (including stereo-image pairs).

An option exists within the lighting model to assign optical transparency to specific parts. Figure 3 illustrates this option in which the armor has been made nearly 100% transparent. This makes viewing of the internal components possible. Some reflection has been given to the armor so that it can be seen. Many other options are available including viewing only certain subsets of geometry and supporting animation for motion studies.

### 1.5 Other CAD Issues

There are many ramifications to the development and exploitation of this technology:

- **Level of Detail:** These CAD tools were originally developed simply to generate target descriptions more quickly. However as higher resolution geometry could be supported, many new and important applications have been developed.
- **Portability** The BRL-CAD package now operates over a dozen computer architectures spanning the range from \$10K single-user workstations to \$20M supercomputers. The ability to retarget code to new machines quickly has made it possible to exploit more fully the growing wealth of DoD computing resources and at the same time avoid "vendor lock in" to a narrow or cost-ineffective hardware base.
- **Extensibility.** Since the software is "owned" by the government, source code is available to all users. Required extensions and modifications can be made by users of the code. New applications typically require new features or extensions.
- **Applications Codes:** There is a large body of applications codes which are linked to the BRL-CAD environment. Following sections will review some of the more prominent ones.
- **Distribution:** To date over 450 computer sites, Government, academia, and industry, have requested and been sent full source code. As new applications

have been found and limits tested, feedback from users has contributed to enhanced releases.

- **Sharing of Geometry:** Even under the best of conditions, the generation of complex target descriptions is an expensive investment. However as workers share geometry, an economy-of-scale develops. Some analyses have been made possible because the geometry has been available when a specific need has arisen. In addition, since the BRL-CAD package is now in use at a significant number of contractor sites, an option exists for the Army to require a compatible digital database with contract deliverables. This greatly reduces the time required to analyze, for example, concept systems and production improvements.
- **Networking:** The CAD package makes copious use of the same intermachine networking standards as used in the DARPA MILNET/ ARPANET. This means that multiple machines both within a single laboratory or literally across the country can exchange files, share databases, and even aggregate computing power for high-demand tasks.

## 2. VULNERABILITY/LETHALITY (V/L) OVERVIEW

The *vulnerability* of a combat system is an assessment of its susceptibility to damage given a specific encounter with a particular threat. Therefore the term *vulnerability* is associated with the ability of military systems to continue fighting subsequent to an interaction with a lethal mechanism delivered by an opposing force. By contrast, *lethality* is the effectiveness with which an attacking weapon can inflict damage on a particular target.

The assessment of vulnerability plays a key role in many Army studies including:

- Concept Tradeoffs
- Vulnerability Reduction & Lethality Optimization
- Inputs to War Games
- Cost & Operational Effectiveness Analyses (COEAs)
- Spare Parts Requirements for Repair of Battle Damage
- Logistics

Over many years the requirements for weapons life-cycle support in the area V/L have resulted in a set of estimation tools. We give a listing in order of increasing complexity:

- Penetration Performance
- Lumped Parameter Probability of Kill Modeling
- Expected-Value Point Burst Modeling
- Spare Parts Estimation
- Stochastic Point-Burst Modeling




Figure 1. Frontal view of the Bradley Armored Fighting Vehicle built and viewed with the BRL-CAD package. The exterior geometry is highly detailed so as to support high-frequency radar and optical simulations. (*Geometric modeling by K. Applin, BRL.*)




Figure 2. Rear view of the Bradley.




Figure 3. Transparent rendering of the Bradley Armored Fighting Vehicle. Using the same target description file as in Fig. 1, a lighting model option allows armor to be rendered transparent, revealing internal component placement.



## 2.1 Penetration Performance

Probably the most fundamental vulnerability question that can be raised about an Armored Fighting Vehicle (AFV) pertains to the protection from threat munitions afforded by its armor. The first figures of merit computed at the early concept phases of an AFV are usually protection levels for various threats vs. the ballistic hull and turret (BH&T). In order to accomplish this a number of inputs must be assembled. The threats must be specified, this task is the province of the Intelligence Community. The target geometry must be constructed using the CAD tools discussed in section 1.3. Finally appropriate warhead/armor algorithms and data must be identified for the threats to be analyzed.

Figure 4 illustrates a concept target description generated for the Mobile Protected Gun System (MPGS) program a few years ago. Ignoring for the moment the exterior suspension system and interior components such as the crew, main gun, fuel, etc., this geometry is appropriately detailed to support penetration calculations. Table I illustrates the status of knowledge for various armor/threat pairings. In the case of some of the more advanced technology combinations, insufficient data exist and vulnerability analysts must make projections.

Once the target geometry and threat performance information is constructed, a BH&T study can proceed. Normally a four-inch grid is projected onto the target from a series of standard aspect angles. A single shot-line is passed through each cell of the grid and the penetration performance calculated. Figure 5 illustrates a cell plot for an AFV for three horizontal attack azimuths. For the case of perforation, the cells can be color-coded according to the magnitude of residual penetration.

## 2.2 Framework for Vulnerability Assessment

The systematic study of AFV vulnerability originated during the 1950's when many firings of antitank rounds were performed against full-scale tanks. By 1960 over 1400 firings had been completed. A *catastrophic kill* (K-Kill) was defined as the total loss of the vehicle through explosion or burning. However it was observed that penetration into interior AFV space did not necessarily result in total vehicle loss. As a result, new measures of effectiveness called probability of kills (or PKs) were developed for mobility and firepower functions. A *firepower kill* (F-Kill) results from an inability to deliver controlled fire within 10 minutes of being hit and the dysfunction is not repairable by the crew on the battlefield. A *mobility kill* (M-Kill) results from an inability to execute controlled movement within 10 minutes of being hit and the dysfunction is not repairable by the crew on the battlefield.

The steps in the vulnerability logic process can be shown as:

- 1] Threat/Target Interaction →
- 2] Component Damage State(s) →
- 3] Loss of Automotive/Firepower Capabilities →
- 4] Probability of M-Kill/F-Kill

Step 1] defines a particular warhead/target combination. After a shot, a set of damaged components may be encountered (Step 2]. If components or systems are killed which support mobility or firepower, there may be partial or total loss of these functions (evaluated in Step 3]). The reduction in these measures of performance (MoPs) is then related to a probability of M- or F-Kill (Step 4]). During the late 1950's, an armor board was convened to develop relationships between severity of AFV damage and M- and F-Kill values. The result of that study was the *Standard Damage Assessment List (SDAL)*; it relates damage in Step 2] to PKs in Step 4] and in modified form is still in use today.

## 2.3 Lumped Parameter Modeling

The AFV tests of the 1950's together with the kill definitions and SDAL were used to develop the first ground vehicle vulnerability model. Called the *Compartment Code*, the model is built on the following data inputs.

- Simple geometry such as shown in Figure 4. The BH&T, exterior suspension, main gun, ammunition and fuel must be represented explicitly.
- Penetration relations for the warhead/armors under evaluation.
- Compartment damage correlation curves.

The correlation curves have been developed from field tests and, in effect, relate the warhead/armor interactions of Step 1] directly to PKs given in Step 4]. The Compartment Code methodology accounts explicitly for warhead penetration at the impact point. This process is used to estimate the probability of a K-Kill due to possible residual penetration interaction with ammunition or fuel. However the effects of all other damage mechanisms, including Behind-Armor Debris (BAD), are lumped into the correlation curves. These curves are then used to make the M- and F-Kill estimates. The model is efficient to run, and over many years the BRL and other organizations have used it as the principal AFV assessment tool. However, because of the way in which many complex damage mechanisms combine in a full-up field test, this model can only be used to predict shots for warhead/targets which have already been fired! Its extrapolatory capability to new vehicle configurations (e.g. spall liners, new armors) and/or new weapons is limited.

Although the outcome of any given ballistic event can be highly random, this model is built by averaging over many samples of field data. Thus lumped-parameter modeling yields an *average* (or first-moment) predictor of PK




Figure 4. Concept design for a Mobile Protected Gun System (MPGS). Inspired by four prior TACOM designs, this BRL variant utilized a mix of rolled homogeneous armor (RHA), reactive, and ceramic armors. Although offering greater protection than the initial designs, the weight burden was increased by five tons. This level of geometric modeling is used to support penetration and lumped-parameter (e.g. Compartment Code) vulnerability analyses. *(Geometric model due to J. Anderson, BRL.)*

Table I. Status of Penetration Data. The matrix shows the status of penetration knowledge for each armor/warhead combination.

ARMOR TYPE	WARHEAD			
	Conventional Shaped Charge	Kinetic Energy Penetrators	Shaped Charge W/Crossing Vel	Tandem Shaped Charges
Homogeneous Steel	3	3	2	2
Homogeneous Aluminum	3	3	2	2
Spaced Configurations of Steel or Aluminum	3	3	2	2
Laminates of Steel and Ceramics or Plastics	1	1	1	1
Single Element Reactives	2	2	2	2
Multiple Element Reactives	2	1	1	2
Reactive Appliques Over Steel/Ceramic Laminates	1	1	1	1
Special Armor	3	3	2	2
				1

Legend:

- 1) No analytical penetration models exist. Critical data voids exist.
- 2) Rudimentary models exist. Additional data are required.
- 3) Extensive data available. Additional data are of some importance.




Figure 5. Standard cell plot used to display various estimates obtained from vulnerability analyses. Three views of a target are shown: 0, 30 and 60 degrees attack azimuth, 0 degrees elevation. From each of three views, a 4" x 4" grid is superimposed on the target geometry. A single shot is fired into each cell. For ground systems optional outputs include a) residual penetration, b) probability of catastrophic kill (P of K-Kill), c) probability of mobility kill (P of M-Kill), and d) probability of fire-power kill (P of F-Kill). (Calculations by J. Ploskonka, BRL.)

## 2.4 Expected-Value Point Burst Modeling

Because of the Compartment Code limitations, vulnerability analysts beginning in the 1970's sought a form of simulation which could be constructed from a series of ballistic submodels rather than built on data from full-up firings. This model would have the potential to evaluate AFVs significantly different from previously tested systems. The cost for this extensibility is the vital need for complete BAD and component-kill data bases.

Called *Expected-Value Point Burst* or in some cases *Component Models*, this class of simulation estimates explicitly both the effects of behind-armor warhead residual and debris.

To support Point-Burst vulnerability assessment, the following inputs must be assembled:

- A highly detailed target description. Every component (both critical and shielding) of the system must appear explicitly. If components are missing, they can't be assessed, and the final results may be biased towards a low estimate of vulnerability. Figure 6 illustrates the interior of an Abrams target description capable of supporting this level of assessment.
- As in simpler models, penetration relations are needed for all warhead/armor pairings that will be encountered; also for all components.
- BAD relations describing spall generation for all armor burst conditions as a function of penetration encounters.
- Component PK assessments for all vehicle critical components (those which support mobility or firepower functions). The form of the component PK characterization and the means used to describe the BAD must be compatible.
- A set of fault trees (or "wiring diagrams") which reflect the system function of all critical components. In the course of the computer simulation, if a given critical component is judged to have been killed, the accompanying fault tree shows whether residual mobility or firepower functions remain.

In the last decade a half-dozen variants on the Point-Burst model have been generated which differ only in the manner in which spall and component PKs are characterized. The status of BAD knowledge is given in Table II.

In addition to the detailed inputs, computer run time increases markedly, mainly due to the shot-line interrogation of the high-resolution target description needed to model the spall process. As in the case of the Compartment Model, the output of these models is an estimate of *expected* M and F PKs.

## 2.5 Spare Parts Estimation

During the past ten years, interest has grown in the areas of battle-field resupply and spare part stockpiling. The point-burst methodology described above was modified to account for two metrics: component damage

sufficient to warrant replacement and required repair time. In effect the component PK metrics of the Point-Burst methodology were lowered to reflect a damage threshold rather than a kill condition.

The input detail and run constraints for Spare Parts Estimation are commensurate with Point-Burst methods.

## 2.6 Stochastic Point-Burst Modeling

In the last few years, many live-fire test programs have been initiated as a result of the National Defense Authorization Act for FY 1987. One of the earliest AFVs tested with overmatching munitions was the Bradley Fighting Vehicle. When the BRL was confronted with the requirement to predict each of some 150 shots before the actual firings it chose an existing (Expected-Value) Point-Burst Code. Since the Bradley had never been extensively tested with overmatching munitions, exercising a version of the Compartment Model was not possible.

When the field-derived PKs were compared with the estimates from the model, certain variations were observed. Critics of vulnerability modeling rated the quality of predictions in terms of the percent variation with field value.

There were three substantial problems at the time in using the extant Point-Burst models in support of live-fire testing:

- Lack of Randomness: Some reflection on the complexity of the destructive processes of ballistic vulnerability soon leads one to the conclusion that there are many aspects of armor penetration, fracture, spall generation, and component dysfunction that could lead to significant shot-to-shot variability were it possible to repeat a given shot configuration many times. In practice the costs of testing and the availability of expensive materiel mean that precision repeated shots are a rarity.
- No Predicted Component Kill Combinations: The extant Point-Burst models predicted the probability of killing components *individually*, but not the probability of killing components by specific *groups*. And it is the latter which is the primary observable in Live-Fire testing.
- Improper Use of Statistics: Various critics of vulnerability modeling rated the quality of assessments by comparing directly the single field PKs with the (first-moment) predictions. This is the equivalent of comparing a single sample from a gaussian (bell curve) distribution with the average of the same curve, no useful inferences can be drawn.

At the onset of the Abrams Live-Fire program, a new stochastic point-burst code called SQuASH was developed. This is a Monte Carlo code which varies a) penetrator hit location over a small area, b) magnitude of warhead performance, c) deflection of residual penetrator, d) the statistics of spall generation, and e) the component PKs.

SQuASH was used to predict the 48 Abrams live-fire shots. Although the model predictions and field




Figure 6. Front-left elevated view of the current Abrams target description with the armor and main armament stripped away. Generated to support high-resolution point-burst vulnerability analysis, this description is composed of some 5000 individual components including hydraulic lines and electrical wires. (*Geometric model due to C. Dively, S. Henry and J. VanDerbeek, BRL.*)

Table II. Status of Behind-Armor Debris (BAD) Data. The matrix shows the status of BAD knowledge for each armor/warhead combination.

ARMOR TYPE	WARHEAD				
	Conventional Shaped Charge	Kinetic Energy Penetrators	Shaped Charge W/Crossing Vel	Tandem Shaped Charges	Explosively Formed Penetrators
Homogeneous Steel	3	2	1	1	3
Homogeneous Aluminum	3	2	1	1	1
Spaced Configurations of Steel or Aluminum	2	1	1	1	2
Laminates of Steel and Ceramics or Plastics	1	1	1	1	1
Single Element Reactives	2	1	1	1	1
Multiple Element Reactives	1	1	1	1	1
Reactive Appliques Over Steel/Ceramic Laminates	1	1	1	1	1
Social Armor	2	2	1	1	1

Legend:

- 1] No analytical behind-armor debris models exist. Critical data void exists.
- 2] Rudimentary models exist. Additional data are required.
- 3] Extensive data available. Additional data are of some importance.

observations are still being analyzed, it is clear that an extraordinarily large number of variations in component damage can occur in live-fire testing. In one shot simulation more than 1.8 million distinct damage states were calculated as possible outcomes (Step 2], 2.2 Framework). When these damage states were mapped via the SDAL to generate PK histograms, disperse and ill-behaved statistics were observed. In some cases 20% of the PKs were zero, another 20% were unity, and the rest were distributed between the extremes. Not atypically, the average PK (first-moment) occurs where not a single outcome is found!

Much more work, both analytical and experimental, will be required to provide precise uncertainty limits on this class of computation.

### 2.7 Summary of Vulnerability Methods

We have reviewed here a set of item-level vulnerability tools used mainly to evaluate AFVs for various direct-fire threats. Although the nature and relative importance of certain damage mechanisms are different, a similar set of codes can be found in the evaluation of air targets. In general as an item moves from concept towards development and beyond, the vulnerability assessments become more detailed and resource intensive. Table III gives time bounds (in man-months) required for the various models described above.

## 3. PREDICTIVE SIGNATURES

In this section, some techniques of predicting military signatures will be described. The methods used can be considered variations on the general approach to item-level modeling previously described.

### 3.1 Optical Lighting

In a previous section the BRL-lighting model was used to create simulated optical images of various military targets. With this lighting calculation, the amount of specular (shiny) or diffuse (rough-surface) reflections can be adjusted to simulate virtually any material, covering or illumination condition. Transparency, illustrated with glass armor, was also demonstrated.

The lighting model can also support a geometric configuration in which an optical beam is directed towards a target from one direction while viewing takes place from another. This configuration is typical of laser-designator studies of the type needed to support the Copperhead laser-guided artillery projectile. The Bradley vehicle description is used to illustrate this capability in Figure 7. The optical scattering pattern is distributed across the turret while the target outline is rendered in wire-frame mode so that its orientation can be inferred.

A second optical prediction result is shown in Figure 8. Here the Bradley target description is used to show the view from an overhead optical sensor as might be encountered in a smart-munitions simulation. The Bradley

has been placed on a ground plane and an optical source simulating the sun positioned above. Image 8a (upper left) shows a high-definition image, complete with ground shadow. To illustrate the processing methods used to simulate noise and resolution constraints, the image given in 8a was modified via an algorithm which introduces noise. The result is shown in Figure 8b (upper right). Next a sequence of two optical filtering operations was performed to reduce the image resolution. The final result is shown in Figure 8c (lower left).

There are also methods to take a two-dimensional image (such as a camouflage pattern) and transfer it onto the surface of a target description. This procedure might be used to support optical pattern recognition studies.

### 3.2 Infrared Modeling

Predictive signature modeling can be extended to other wavelength regions. Figure 9 illustrates a simple procedure which shows how the utility of measurements can be extended greatly. In the upper image, an infrared (IR) image is shown of an actual Soviet T62 tank. The temperatures inferred by measurement are made visible by false-color imaging. A calibration bar below the image gives the appropriate color-temperature associations. To give greater utility to these measurements, a target description of a T62 has been configured identically to the measured vehicle to include the same gun-elevation angle. In a special mapping procedure, the measured temperatures (top) have been mapped (transferred) to the target geometry (below). Through this procedure, the target can be viewed from angles other than that of data capture; in addition, the target thermal performance can be extrapolated to other IR bands via standard algorithms of radiation physics.

Over the past few years the Keweenaw Research Center and TACOM have developed a predictive IR model. Work is currently in progress to replace many of the tedious manually prepared inputs with geometric and material data converted automatically from BRL-CAD target files.

### 3.3 Radar Modeling

The final examples of predictive signatures involve the calculated radar properties of military targets. Historically radars were used to infer target range and closing rates. For the early radars, a figure of merit, the radar cross section, was of key importance, as it represents the efficiency with which radar waves are scattered back to the receiver. Certain modern radars, when placed on moving platforms such as aircraft, can be used to form a two-dimensional image of targets. Radar imagery of this class is called synthetic aperture radar (SAR). A description of an M48 tank has been analyzed with a SAR program (due to the Environmental Research Institute of Michigan), and the results are shown in Figures 10 and 11. In the upper right of Figure 10 the orientation of the target vehicle is shown as seen with respect to the radar. A horizontal flight path (left to right) is assumed. The properties of SAR processing are such that following signal detection and manipulation an image is derived which resolves the



Table III. Models *vs.* Input requirements/preparation times (in months). All estimates assume the availability of a) Intelligence Community validated threat specification and b) detailed item configuration specification by the system advocate.

ANALYSIS TYPE	RESOURCE						
	Target Description ( <i>ab initio</i> )		Penetration Relations/ Data Bases		BAD Relations/ Data Bases <sup>†</sup>		Total El Time
	Total Man-Mths	Min El Time <sup>‡</sup>				Component/ System Logic	Component PKs
Penetration Performance	3	1	0.5 - 1	0	0	0	0
Lumped Parameter PK	4	2	0.5 - 1	0	0	0	5
Exp Value Point Burst	16 - 18	9 - 12	0.5 - 1	3 - 6	4 - 6	6 - 12	11 - 14
Spare Parts	20 - 22	10 - 14	0.5 - 1	3 - 6	4 - 6	6 - 12	12 - 16
Stochastic Point-Burst	16 - 18	9 - 12	0.5 - 1	1 - 2	4 - 6	1 - 4	11 - 14

<sup>‡</sup> With multiple analysts, total elapsed time can be compressed.

<sup>\*</sup> Depends on availability of data. See Table I.

<sup>†</sup> Depends on availability of data. See Table II.




Figure 7. Simulation of a laser designator on the Bradley vehicle. Using the model, any target surface condition or illumination/viewer orientations can be used. (*Lighting model result due to G. Moss, BRL.*)




Figure 8. Simulation of an overhead smart-munition sensor. A ground plane has been placed under a Bradley vehicle with the sun positioned overhead (upper left). Noise has been mixed with the first image (upper right). In the lower left image, filtering operations have been performed to reduce the (simulated) resolving power of the sensor. (*Lighting model result due to G. Moss and E. Davisson, BRL.*)




Figure 9. Upper image shows IR field data of Soviet T62 tank. Lower image shows the field data mapped onto the surface of a target description. With this method, thermal images can be generated for other viewer positions and thermal regions. (*IR model result due to G. Moss, BRL.*)




Figure 10. Two images of an M18 tank: which illustrate the synthetic aperture radar (SAR) process. In the upper-right is the target as viewed by the radar. Below is the image orientation after radar processing. (Images due to E. Davisson, BRL.)




Figure 11. High-resolution SAR images of an M48 tank. In both images, cross range is plotted against range. On the left, the vertical/ vertical (vv) polarization components are shown; on the right, the vertical/ horizontal (vh). (Images due to E. Davisson, BRL.)

target in range and cross-range (along the flight path) but not in the remaining orthogonal direction. Thus the final SAR image orientation is similar to the optical rendering shown in the bottom left of Figure 10. A pair of computed SAR images for the M48 is shown in Figure 11. The labels vv and vh represent two combinations of transmit/ receive polarization (vertical/ horizontal) states. In addition, these calculations have been made in a high-resolution mode (about two-inch resolution) and are not constrained by practical frequency or coherence considerations of realizable radar systems. In each of these images, the radar signal is propagating from left to right. Range information is plotted along the abscissa and cross-range data along the ordinate.

The scattering of radar waves is determined by both target shape and material composition. Flat surfaces, particularly in combination, tend to reflect radar waves efficiently in preferred directions. A number of programs have been written to extract from target descriptions those surface shapes which are 1) flat only and 2) have dihedral (right-angle) elements. The information provided by these programs can be used as input to certain radar models as well as providing guidance in the minimization of signal return from US systems under design.

Finally, predicting the performance of high-frequency radars can be particularly challenging because of the geometric detail required as frequency increases. A tool which is finding increasing utility is illustrated in Figure 12. The objective is to characterize radar scattering at 94 Ghz to support smart munition as well as armored-fighting vehicle design. In the upper right portion of Figure 12, a US M109 self-propelled howitzer is shown from the left rear. This is an optical image of the actual vehicle. The middle right image is a plot derived from a 94 Ghz scanning radar (6-inch target resolution) set in a co-polarized mode. The cross-polarized mode is shown in the bottom right. To simulate this process, a target description of an M109 was built to a high-level of detail including high-resolution tracks and suspension system. This target was viewed from the same orientation as the actual optical image (upper right) and is shown in the upper-left corner. Using the lighting model described above, the target was given the properties of a purely specular (mirror-like) object. A single light source at the view position was used. The middle-left image shows the results. A glint image, highly suggestive of the right middle and lower images, is shown. The middle left image was low-pass filtered to achieve an even greater similarity with the field data shown on the right.

### 3.4 Summary of Signature Methods

This has been a brief review of some state-of-the-art techniques for predicting military signatures. The general methods share an approach used for many other kinds of high-resolution calculations in item-level analyses. The procedure is based on the construction of computer files representing three-dimensional geometry and related material properties. These files are then linked to a particular application code based on the required signature, viewing angle, and other physical attributes.

## 4. OTHER ITEM-LEVEL ANALYSES

Of all item-level applications, the vulnerability and signature methods are the most heavily exploited by the weapons modeling community; nevertheless the possibilities and potential impact of this class of modeling goes far beyond these two disciplines. In this section, a brief review will be made of other item-level applications which have been developed to date. Finally, some of the possibilities and issues connected with growing utilization of item-level modeling will be discussed.

### 4.1 Other Application Codes

- **Weights & Moments-of-Inertia:** As noted previously, when a target description is assembled, both the geometric shapes (internal as well as external) are fully defined. In addition, each geometric entity of the description is assigned a unique name to which specific material properties are related. For the task of weight estimation, the material density of each component or part is linked to the geometry. By firing mathematical rays in a tight grid and viewing groups of these rays, the composition of a target can be seen in high resolution. Figure 13 illustrates this process in which a 1" x 1" matrix of rays was fired through the front of a heavy tank target description. Groups of rays in horizontal sections were then extracted for individual viewing. Two are shown; the various gray levels (normally rendered in color) indicate the specific target materials (armor, ammunition, fuel, crew, air, etc.). If the material density information used for viewing is integrated over all rays in a given section, the weight of the target is derived for that particular one-inch thickness. If all sections are added, the weight of the entire system is estimated.

Such a process is important in many stages of weapons system evaluation. In all military systems, whether conceptual or fielded, air or ground, weight is a critical constraint.

By similar methods the Center-of-Mass and the Moments-of-Inertia (Mol) of a system can be estimated as well. The Mol are a measure of the torques required to change the rotational rate of a mechanical assembly.

The BRL-CAD tools have been used, for example, to estimate 1) the baseline weight of an M60, and then 2) the change in weight for various configurations of applique armor. In addition, Mol calculations were performed with the applique layouts in order to estimate the required changes in the turret slewing hydraulics. These methods have also seen application in problems such as estimation of vehicle overturning moments due to nuclear (air) blast wave and a howitzer undergoing firing cycles.

- **Neutron Transport:** When a nuclear weapon is detonated, several threats to equipment and personnel exist. Among these is nuclear radiation. Using a computer code developed at Oak Ridge National Laboratory, the initial radiation output from a nuclear weapon can be tracked from the point of detonation to a region within a military vehicle.




Figure 12. Comparison of 94 Ghz radar data with simulation for M109 self-propelled howitzer. Right-hand images are field-derived; left-hand are simulations. (Experimental data due to H. Wallace, BRL, predictions due to T. Karr and E. Davisson, BRL.)






Figure 13. High density shotline sections through a tank target description; various line shadings denote different material densities. (Calculations by R. Suckling, BRL.)

A number of years ago this code was used to estimate the neutron dosage just below the driver's hatch in a concept vehicle. Called the Tank Test Bed, one particular configuration is illustrated in the upper half of Figure 14. In this study, the total radiation dose reaching the driver's head was calculated while monitoring the specific exterior portions of the vehicle through which the radiation leaked. In the lower half of Figure 14 the image shading has been adjusted according to the magnitude of neutron flux. Higher neutron flux surfaces are shown in lighter shades.

- **Structural/Acoustic Analysis:** Structural integrity is an important issue in the design, analysis and testing of military items. It is clearly a central issue for both fixed and rotary-wing aircraft; in the past it has not been an issue for heavy tanks, but now has taken on increasing importance with lighter fighting vehicles, particularly as the use of explosive applique armor has been considered.

A baseline calculation is often employed to yield the so-called "static case" in which a steady force is applied to a portion of a vehicle. Such a pilot study was performed using a chassis design for a Mobile Protected Gun System (MPGS). The BRL-CAD geometry assembled for vulnerability analysis was translated into the CAD format of a commercial finite-element preprocessor (PATRAN<sup>TM</sup>). Inside this modeler the chassis was subdivided into discrete elements and then passed to a finite-element code (ADINA<sup>TM</sup>) where a steady force corresponding to the turret weight was applied to the region of the turret ring. Figure 15 below shows the von Mises stresses calculated over the chassis. The results reveal a conservative design, far below the levels at which plastic deformation begins.

The same finite-element medium can be used for other classes of calculations. One study performed involved calculating the natural harmonic frequencies of this chassis design together with the amplitudes of oscillation. Such results can be important in reducing harmonic resonances which can affect vehicle mobility; they relate as well to the acoustic signature of the vehicle.

- **High-Energy Laser.** In the 15 years prior to 1984, many high-energy laser experiments were carried out, these tests established an effects data base for lasers of various wavelengths (primarily 10.6 and 3.8 microns) and wave shapes (pulsed and continuous). During the same time vulnerability tests were conducted to establish component-damage thresholds, particularly for those utilized in optical systems, missiles and aircraft. The information gathered in this testing has been used to assemble a laser-damage effects model BRL-CAD target descriptions, giving the three-dimensional geometry and material definitions, serve as part of the input. This information is combined with illumination dwell times and damage thresholds to compute likelihood of component degradation/ target destruction.
- **High-Powered Microwave (HPM).** HPM weaponry is currently in the exploratory research stage. The coupling of microwave energy to the components of a target is an extremely complicated, non-separable

problem. Linkage can occur via "front-door" avenues, such as through antennae which are designed to collect low power microwave signals, or through "back-door" channels, such as cracks and seams in the outer vehicle skin. These potential channels and their unavoidable interplay result in the need to analyze systems as a whole in order to achieve reliable target kill assessments. A goal for HPM is development of a computer-based methodology which uses the standard BRL-CAD target models (perhaps with some augmentation) in the assessment of target vulnerability. The development of a computer model has been contracted for and the first-stage deliverables are under review.

- **X-Ray Simulation.** Recently an extension was made to the BRL-CAD environment to simulate the behavior of X-rays in materials. The radiation source can be placed at an arbitrary point in space. A series of rays are then extended through the object for which the simulation is to be performed. The material attributes assigned to the regions of the object can be related to actual X-ray absorption. Thus the energies emerging at the far side of an object can be calculated and then transformed according to the efficiencies typical of film detection. Images have been derived for a number of objects including portions of heavy tanks. Such techniques may be of aid in the interpretation of experimental X-rays normally taken in armor penetration studies or other noninvasive tests.

The techniques described here and in the previous sections represent current methods of high-resolution item-level modeling. By inference, many other kinds of applications can be supported, limited only by the imagination of the analyst.

#### 4.2 Planned BRL-CAD Upgrades

The capabilities of the current set of tools derive mainly from the distinct requirements of the vulnerability and signature communities. However it is recognized that there are specific extensions which would bring the utility of these tools to other users with their own distinct requirements.

- **Blueprints:** For a significant number of weapons analysts today, the world of CAD means aiding the process of blueprint generation. Although the BRL-CAD tools can generate elegant optical images as well as the simpler scaled "wire-frame" drawings, such output falls far short of the requirements for dimensioning, tolerancing, and other standard fare of the industrial-design world. Two approaches to gaining this capability are being examined. One involves generating blueprints directly from a BRL-CAD data base via a set of stand-alone software. The other approach involves creating a mapping code capable of transforming target descriptions generated with BRL-CAD into a format used by a second modeling system already capable of blueprint generation.




Figure 14. Neutron transport calculations for a concept heavy tank. (*Prediction due to J. Kinch, BRL.*)




Figure 15. Structural calculations for a concept light-armored vehicle. (Prediction due to E. Quigley, BRI.)

- **3-D Mesh Generation.** The origins of the current set of BRL-CAD software arose 20 years ago in order to support vulnerability and neutron transport analyses. The way in which the early analysts chose to link the target descriptions with the applications codes was through ray casting (or ray tracing). This method fits conveniently the notion of bullet and neutron trajectories, and indeed the majority of codes illustrated in this article use ray casting as the means of connection.

There exists, however, an important body of applications codes which, rather than depending on ray tracing, require geometry described in terms of a regular collection of facets, or flat approximations to the actual geometric surfaces. The BRL has initiated a project to develop software capable of transforming the standard form of target descriptions into one composed entirely of such facets; the size or coarseness of such facets would be set by the user.

The success of this project could open important new avenues of analysis. For example, some predictive thermal codes (such as the PRISM model developed at TACOM) require facets as the basic building block for analysis. Certain radar codes (such as one in use at Northrop) require a target model composed of facets so that numerical integration methods can be applied directly to the geometry. Also many of today's most powerful interactive computer workstations have on-board hardware capable of performing real-time image generation for geometry supplied in a facet format.

#### 4.3 Future Issues

Currently the AMC has a renewed interest in CAD. A charter for an AMC Functional Coordinating Group for Computer Aided Design-Engineering (CAD-E) was approved on 24 February 1989. The CAD-E Group is directed to make a strategic assessment of AMC CAD-E efforts, evaluate the feasibility of a standard CAD-E system and determine how such a system would be maintained.

An issue which is always problematic involves the extent to which standards should be imposed on a particular community of users. Without some standards, interchange of data may become difficult or impossible.

The plethora of ways in which geometry can be represented is in fact the reason solid geometric data generated by one commercial modeling system generally cannot be used by another vendor's system. Sometimes the basic geometric constructs used in one system simply cannot be exactly handed over to another due to mathematical constraints. Another typical incompatibility arises because most vendors choose to keep the nature and format of their data base inaccessible to the user. This is a commercial strategy referred to by some as "vendor lock in". The government-supported Initial Graphics Exchange Specification (IGES) has been moderately successful at defining standards for sharing wire frame (or drafting-level) geometry but is unlikely to provide a common meta-language specification for the solid modeling world.

The approach taken in the BRL-CAD environment has been to modularize those parts of the software in which the mathematical definitions of 3-D shapes play a role. Tools have been developed so that as new mathematical forms are required, they can be added easily at these key sections of code. All other parts of the environment, including interfaces to applications codes, remain unchanged.

The first foray into using BRL-CAD as an Army standard begins now with the Heavy Forces Modernization (HFM) thrust. The objective of HFM is provide the Army with the optimum ground-vehicle fleet in the year 2004; nearly 30 vehicle types are included. All vendors will be required by contract to submit geometric and material descriptions of vehicle designs in the BRL-CAD format and to provide updates at six-month intervals.

On the other hand, with too many standards, technical innovation can be stifled. Such a situation could arise in a future weapons procurement if both a solid-modeling requirement and the new DoD Computer-Aided Acquisition and Logistics Support (CALS) system are applied. CALS is a laudable interservice effort to provide standards for computer-aided design drawings, text formatting, graphics and pictures. However since solid geometric data is a complete form of specification as opposed to blueprint-level specification, the former is not derivable from the latter. If the latter were defined to be the primary deliverable under a government contract, it might well preclude the use of the more advanced technology. These and related issues will provide interesting challenges as the electronic age advances.

In a time of shrinking resources, the maintenance of BRL-CAD software and related data bases is receiving increasing attention. At least three aspects are involved:

- [1] The CAD package itself has been distributed to over 450 computer sites. Code and documentation must be written and distributed, bug-fixes performed, and extensions made as new capabilities are sought.
- [2] Various inhouse applications codes (vulnerability, signature, etc.) must be maintained, extended, and distributed within a growing community of users. Also codes developed by outside users need to be brought in, examined, and sometimes installed for inhouse production use.
- [3] Among the community of target-description providers [BRL, Denver Research Institute (see Section 1.3), and other contractors] there now exist hundreds of military target descriptions, domestic and foreign, in a shareable format. Mechanisms must be found and implemented for storing, sharing and upgrading these valuable assets.


#### 4.4 Summary of Other Application Codes

In this review, many modern computer-based methods have been described in support of high-resolution item-level weapons modeling. Without doubt these methods will enjoy increasing use both throughout government and industry. This exploitation is possible because of a number of factors including the establishment of rigorous

algorithms, the uniform support provided by modern computer software environments, and the power and low cost of today's computer hardware

The development of these tools is due to the efforts of many scientists and analysts, it is significant that a major portion of these modern analytic methods owe their existence to Army-sponsored and staffed research.

Dr. Paul H. Deitz is Chief of the Vulnerability Methodology Branch, Vulnerability/Lethality Division, of the USA Ballistic Research Laboratory. He holds a bachelor's degree in physics from Gettysburg College and masters and Ph.D. degrees in electrical engineering from the University of Washington.



	<u>No of</u> <u>Copies</u>	<u>Organization</u>		<u>No of</u> <u>Copies</u>	<u>Organization</u>
(Unclass., unlimited)	12	Administrator		1	Commander
(Unclass., limited)	2	Defense Technical Info Center			US Army Missile Command
(Classified)	2	ATTN: DTIC-DDA Cameron Station Alexandria, VA 22304-6145			ATTN: AMSMI-RD-CS-R (DOC) Redstone Arsenal, AL 35898-5010
	1	HQDA. (SARD-TR) WASH DC 20310-0001		1	Commander
	1	Commander US Army Materiel Command ATTN: AMCDRA-ST 5001 Eisenhower Avenue Alexandria, VA 22333-0001			US Army Tank-Automotive Command ATTN: AMSTA-TSL (Technical Library) Warren, MI 48397-5000
	1	Commander US Army Laboratory Command ATTN: AMSLC-DL Adelphi, MD 20783-1145	(Class. only)	1	Commandant
	2	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-MSI Picatinny Arsenal, NJ 07806-5000			US Army Infantry School ATTN: ATSH-CD (Security Mgr.) Fort Benning, GA 31905-5660
	2	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-TDC Picatinny Arsenal, NJ 07806-5000	(Unclass. only)	1	Commandant
	1	Director Benet Weapons Laboratory Armament RD&E Center US Army AMCCOM ATTN: SMCAR-CCB-TL Watervliet, NY 12189-4050			US Army Infantry School ATTN: ATSH-CD-CSO-OR Fort Benning, GA 31905-5660
	1	Commander US Army Armament, Munitions and Chemical Command ATTN: SMCAR-ESP-L Rock Island, IL 61299-5000	(Class. only)	1	The Rand Corporation P.O. Box 2138 Santa Monica, CA 90401-2138
	1	Commander US Army Aviation Systems Command ATTN: AMSAV-DACL 4300 Goodfellow Blvd. St. Louis, MO 63120-1798		1	Air Force Armament Laboratory ATTN: AFATL/DLODL Eglin AFB, FL 32542-5000
	1	Director US Army Aviation Research and Technology Activity Ames Research Center Moffett Field, CA 94035-1099			<u>Aberdeen Proving Ground</u> Dir, USAMSAA ATTN: AMXSY-D AMXSY-MP, H. Cohen Cdr, USATECOM ATTN: AMSTE-TO-F Cdr, CRDEC, AMCCOM ATTN: SMCCR-RSP-A SMCCR-MU SMCCR-MSI Dir, VLAMO ATTN: AMSLC-VL-D

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
10	C.I.A. OIR/DB/Standard GE47 HQ Washington, DC 20505	1	Office of the Under Secretary of Defense, R&E ATTN: Dr. William Snowden The Pentagon, Room 3D359 Washington, DC 20301
1	HQDA (DAMI-FIT, COL O'Connor) WASH DC 20310-1001	1	Office of the Asst Dep Dir of Defense Live Fire Testing ATTN: COL L. Stanford The Pentagon, Room 3E1060 Washington, DC 20301
1	HQDA (DAMO-ZD, Mr. Riente) The Pentagon, Rm 3A538 WASH DC 20310-0410	2	OSD OUSD (A) ODDDRE (T&E/LFT) ATTN: James O'Bryon Albert E. Rainis The Pentagon, Rm 3E1060 Washington, DC 20301-3110
1	HQDA (SARD-TN, LTC Fejfar) The Pentagon, Rm 3E360 WASH DC 20310	1	American Defense Preparedness Association (ADPA) ATTN: Bill King 1700 N. Moore Street, #900 Arlington, VA 22209-1942
1	HQDA (Asst Chief of Staff for Intelligence, Joseph Varandore) WASH DC 20310-1067	9	Defense Advanced Research Projects Agency ATTN: Mr. B. Bandy Dr. R. Kahn Dr. C. Kelly Mr. P. Losleben Dr. J. Lupo Mr. F. Patten Dr. Reynolds Mr. S. Squires COL J. Thorpe 1400 Wilson Boulevard Arlington, VA 22209
1	HQDA (Limres Study Group, Shirley D. Ford) The Pentagon, Room 1B9C9 WASH DC 20310	2	Central Intelligence Agency ATTN: ORD/PERD (Ray Cwiklinski) (Tom Kennedy) Washington, DC 20505
1	Administrative Support Group Office of the Secretary of the Army ATTN: LTC Douglas R. Milne Room 3D715, Pentagon Building Washington, DC 20310	1	Central Intelligence Agency ATTN: ORD (Jim Fahnestock) Washington, DC 20505
1	Office of the Assistant Secretary of the Army (Research, Development, and Acquisition) ATTN: LTG Donald S. Pihl, Military Deputy Washington, DC 20310-0100		
1	Office of the Secretary of the Army (Research, Development, and Acquisition) ATTN: MG August M. Cianciolo Deputy for Systems Management Washington, DC 20310-0103		
1	Deputy Under Secretary of the Army for Operations Research ATTN: OUSA (Hon Walt Hollis) The Pentagon, Room 2E660 Washington, DC 20310-0102		



# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Central Intelligence Agency ATTN: ORD/IERD (J. Fleisher) Washington, DC 20505	1	Commander US Army Materiel Command ATTN: AMCPD (Darold Griffin) 5001 Eisenhower Avenue Alexandria, VA 22333-0001
1	Central Intelligence Agency ATTN: ORD (Marvin P. Hartzler) Washington, DC 20505	1	Commander US Army Materiel Command ATTN: AMCPD-PM (Jim Sullivan) 5001 Eisenhower Avenue Alexandria, VA 22333-0001
2	Central Intelligence Agency ATTN: OIA (Barbara A. Kroggel) (Monica McGuinn) Washington, DC 20505	2	Commander US Army Materiel Command ATTN: AMCPM-LOTA (Robert Hall) (MAJ Purdin) 5001 Eisenhower Avenue Alexandria, VA 22333-0001
1	Central Intelligence Agency ATTN: ORD (Peter Lew) 1820 N. Fort Meyer Drive Arlington, VA 22209	1	Commander US Army Materiel Command ATTN: AMCSP (COL Barkman) 5001 Eisenhower Avenue Alexandria, VA 22333-0001
1	Chief of Naval Operations OP-03-C2 ATTN: CPT Robert K. Barr Rm 4D537, The Pentagon Washington, DC 20350-2000	1	Commander US Army Materiel Command ATTN: AMCTD-PT (Alan Elkins) 5001 Eisenhower Avenue Alexandria, VA 22333-0001
1	Mr. Robert Gomez/OSWR PO Box 1925 Washington, DC 20013	1	Commander US Army Materiel Command ATTN: AMSLC-AS-TT (K. Zastrow) 2800 Powder Mill Road Adelphi, MD 20783-1145
1	Commander US Army Materiel Command ATTN: AMCDE-PM (Dan Marks) 5001 Eisenhower Avenue Alexandria, VA 22333-0001	1	Commander US Army Laboratory Command ATTN: AMSLC-CG 2800 Powder Mill Road Adelphi, MD 20783-1145
2	Headquarters US Army Materiel Command ATTN: AMCDMA (M. Acton) (R. Black) 5001 Eisenhower Avenue Alexandria, VA 22333-0001	2	Commander US Army Laboratory Command ATTN: AMSLC-CT (J. Predham) (D. Smith) 2800 Powder Mill Road Adelphi, MD 20783-1145
1	Commander US Army Materiel Command ATTN: AMCMT (John Kicak) 5001 Eisenhower Avenue Alexandria, VA 22333-0001		

# DISTRIBUTION LIST

No. of Copies	Organization	No. of Copies	Organization
1	Commander US Army Laboratory Command ATTN: AMSLC-TD (R. Vitali) 2800 Powder Mill Road Adelphi, MD 20783-1145	1	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-FSS-E (Jack Brooks) Picatinny Arsenal, NJ 07806-5000
1	Commander US Army Laboratory Command ATTN: SLCTO (Marcos Sola) 2800 Powder Mill Road Adelphi, MD 20783-1145	1	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-TD (Jim Killen) Picatinny Arsenal, NJ 07806-5000
1	Commander US Army Materials Technology Laboratory ATTN: SLCMT-ATL Watertown, MA 02172-0001	1	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-TDS (Vic Lindner) Picatinny Arsenal, NJ 07806-5000
3	Director US Army Research Office ATTN: SLCRO-MA (Dr. J. Chandra) (Mr. K. Clark) (Dr. Wu) P.O. Box 12211 Research Triangle Park, NC 27709-2211	1	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-TSS Picatinny Arsenal, NJ 07806-5000
1	Director US Army Survivability Management Office ATTN: SLCSM-C31 (H. J. Davis) 2800 Powder Mill Road Adelphi, MD 20783	1	Commander US Army Aviation Systems Command ATTN: AMSAV-ES 4300 Goodfellow Blvd St Louis, MO 63120-1798
1	Director US Army Survivability Management Office ATTN: SLCSM-D (COL H. Head) 2800 Powder Mill Road Adelphi, MD 20783-1145	1	Commander US Army Aviation Systems Command ATTN: AMSAV-GT (R. Lewis) 4300 Goodfellow Blvd St. Louis, MO 63120-1798
1	Director US Army Survivability Management Office ATTN: SLCSM-GS (Mark Rechtes) 2800 Powder Mill Road Adelphi, MD 20783-5071	2	US Army Aviation Systems Command ATTN: AMSAV-NC (H. Law) (S. Meyer) 4300 Goodfellow Blvd St. Louis, MO 63120-1798
1	Commander Armament RD&E Center US Army AMCCOM ATTN: SMCAR-CCH-V (Paul H. Gemmill) Picatinny Arsenal, NJ 07806-5000	1	Commander Belvoir Research, Development and Engineering Center ATTN: STRBE-FC (Ash Patil) Fort Belvoir, VA 22060-5606

# DISTRIBUTION LIST

No. of Copies	Organization	No. of Copies	Organization
1	Commander Belvoir Research, Development and Engineering Center ATTN: STRBE-JDA (Melvin Goss) Fort Belvoir, VA 22060-5606	3	Commander US Army Foreign Science and Technology Center ATTN: AIAFRS (Gordon Spencer) (John McKay) (Chip Grobmyer) 220 Seventh Street, NE Charlottesville, VA 22901-5396
1	Commander CECOM R&D Technical Library ATTN: ASQNC-ELC-I-T, Myer Center Fort Monmouth, NJ 07703-5000	1	Commander US Army Foreign Science and Technology Center ATTN: AIAFRT (John Kosiewicz) 220 Seventh Street, NE Charlottesville, VA 22901-5396
1	Director Center for Night Vision and Electro-Optics ATTN: AMSEL-NV-V (John Palmer) Fort Belvoir, VA 22060-5677	1	Commander US Army Foreign Science and Technology Center ATTN: AIFRC (Dave Hardin) 220 Seventh Street, NE Charlottesville, VA 22901-5396
1	Director Center for Night Vision and Electro-Optics ATTN: AMSEL-RD-NV-V (John Ho) Fort Belvoir, VA 22060-5677	1	Commander US Army Foreign Science and Technology Center ATTN: DRXST-WSI (John R. Aker) 220 Seventh Street, NE Charlottesville, VA 22901-5396
1	Director Center for Night Vision and Electro-Optics ATTN: DELMV-L (Dr. R. Buser) Fort Belvoir, VA 22060-5677	1	Commander US Army Harry Diamond Laboratory ATTN: SLCHD-RT (Peter Johnson) 2800 Powder Mill Road Adelphi, MD 20783-1197
1	Commander US Army Foreign Science and Technology Center ATTN: AIAF (Bill Rich) 220 Seventh Street, NE Charlottesville, VA 22901-5396	1	Commander US Army INSCOM ATTN: IAOPS-SE-M (George Maxfield) Arlington Hall Station Arlington, VA 22212-5000
3	Commander US Army Foreign Science and Technology Center ATTN: AIAFRC (T. Walker) (S. Eitleman) (R. Witnebal) 220 Seventh Street, NE Charlottesville, VA 22901-5396	2	Commander US Army Missile Command ATTN: AMSMI-RD-GC-T (R. Alongi) Redstone Arsenal, AL 35898-5000

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Commander US Army Missile Command ATTN: AMSMI-RD-SS-AT Redstone Arsenal, AL 35898-5000	1	Commander US Army Natick R&D Center ATTN: STRNC-OI (Stephen A. Freitas) Natick, MA 01760
1	Commander US Army Missile Command ATTN: AMSMI-RGT (J. Bradas) Redstone Arsenal, AL 35898-5000	1	Commander US Army Tank-Automotive Command ATTN: AMSTA-CF (Dr. Oscar) Warren, MI 48090
1	Commander US Army Missile Command ATTN: AMSMI-YTSD (Glenn Allison) Redstone Arsenal, AL 35898-5070	1	Commander US Army Tank-Automotive Command ATTN: AMSTA-CK (G. Orlicki) Warren, MI 48090
1	Commander US Army Missile Command ATTN: DRSMI-REX (W. Pittman) Redstone Arsenal, AL 35898-5500	1	Commander US Army Tank-Automotive Command ATTN: AMSTA-CR (Mr. Wheelock) Warren, MI 48397-5000
1	Director US Army Missile and Space Intelligence Center ATTN: AIAMS-YDL Redstone Arsenal, AL 35898-5500	1	Commander US Army Tank-Automotive Command ATTN: AMSTA-CV (COL Kearney) Warren, MI 48397-5000
2	Director US Army Missile and Space Intelligence Center ATTN: AIAMS-YRS, Thomas Blalock Pete Kirkland Redstone Arsenal, AL 35898-5500	2	Commander US Army Tank-Automotive Command ATTN: AMSTA-NKS (D. Cyaye) (J. Rowe) Warren, MI 48397-5000
2	Director US Army Missile and Space Intelligence Center ATTN: AIAMS-YRT, Francis G. Cline Don A. Slaymaker Redstone Arsenal, AL 35898-5500	2	Commander US Army Tank-Automotive Command ATTN: AMSTA-RGE (R. Munt) (R. McClelland) Warren, MI 48397-5000
1	Director US Army Missile and Space Intelligence Center ATTN: Randy L. Smith Redstone Arsenal, AL 35898-5500	3	Commander US Army Tank-Automotive Command ATTN: AMSTA-RSC (John Bennett) (Wally Mick) Warren, MI 48397-5000
		1	Commander US Army Tank-Automotive Command ATTN: AMSTA-RSK (Sam Goodman) Warren, MI 48090-5000

# DISTRIBUTION LIST

No. of Copies	Organization	No. of Copies	Organization
1	Commander US Army Tank-Automotive Command ATTN: AMSTA-VS (Brian Bonkosky) Warren, MI 48090-5000	1	Commander US Army Vulnerability Assessment Laboratory ATTN: SLCVA-CF (Gil Apodaca) White Sands Missile Range, NM 88002-5513
6	Commander US Army Tank-Automotive Command ATTN: AMSTA-ZE (R. Asoklis) AMSTA-ZEA (C. Robinson) (R. Gonzalez) AMSTA-ZS (D. Rees) AMSTA-ZSS (J. Thompson) (J. Soltez) Warren, MI 48397-5000	2	US General Accounting Office Program Evaluation and Methodology Division ATTN: Robert G. Orwin Joseph Sonnefeld Room 5844 441 G Street, NW Washington, DC 20548
1	Commander HQ, TRADOC ATTN: Asst Dep Chief of Staff for Combat Operations Fort Monroe, VA 23651-5000	1	Director US Army Industrial Base Engineering Activity ATTN: AMXIB-MT Rock Island, IL 61299-7260
2	US Army TRADOC Analysis Center ATTN: ATRC-RP (COL Brinkley) ATRC-RPR (Mark W. Murray) Ft. Monroe, VA 23651-5143	1	Director US Army Industrial Base Engineering Activity ATTN: AMXIB-PS (Steve McGlone) Rock Island, IL 61299-7260
1	Director US Army Cold Regions Research and Development Laboratory ATTN: Technical Director (Lewis Link) 72 Lyme Road Hanover, NH 03755	3	Director US Army Engineer Waterways Experiment Station ATTN: WESEN (Dr. V. LaGarde) (Mr. W. Grabau) WESEN-C (Mr. David Meeker) PO Box 631 Vicksburg, MS 39180-0631
1	US Army Corps of Engineers Assistant Director Research and Development Directorate ATTN: Mr. B. Benn 20 Massachusetts Avenue, NW Washington, DC 20314-1000	1	US Army Engineer Topographic Laboratories ATTN: Technical Director (W. Boge) Fort Belvoir, VA 22060-5546
1	Commander US Army Operational Test and Evaluation Agency ATTN: MG Jerome B. Hilmes 5600 Columbia Pike Falls Church, VA 22041	1	Commander US Army Operational Test and Evaluation Agency ATTN: LTC Gordon Crupper 5600 Columbia Pike Falls Church, VA 22041

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
3	Los Alamos National Laboratories ATTN: MS 985, Dean C. Nelson MS F600, Gary Tietgen MS G787, Terrence Phillips PO Box 1663 Los Alamos, NM 87545	4	Commander US Naval Surface Warfare Center ATTN: Gregory J. Budd James Ellis Barbara J. Harris Constance P. Rollins Code G13 Dahlgren. VA 22448-5000
1	Los Alamos National Laboratories ATTN: MS F681, LTC Michael V. Ziehm USMC PO Box 1668 Los Alamos, NM 87545	2	Commander US Naval Weapons Center ATTN: Ed Patterson Dr. Helen Wang Code 3313 Bldg 1400, Room B17 China Lake, CA 93555
1	Sandia National Laboratories Division 1611 ATTN: Tom James Albuquerque, NM 87185	1	Commander US Naval Weapons Center ATTN: Mark D. Alexander Code 3894 China Lake, CA 93556-8001
1	Sandia National Laboratories Division 1623 ATTN: Larry Hostetler Albuquerque, NM 87185	1	Commander US Naval Weapons Center ATTN: Melvin H. Keith Code 39104 China Lake, CA 93555
1	Sandia National Laboratories ATTN: Gary W. Richter PO Box 969 Livermore, CA 94550	1	Commander US Naval Weapons Center ATTN: Tim Horton Code 3386 China Lake, CA 93555
1	US Naval Air Systems Command JTCG/AS Central Office ATTN: 5164J (LTC James B. Sebolka) Washington, DC 20361	1	Commander US Naval Civil Eng Laboratories ATTN: John M. Ferritto Code L53 Port Hueneme, CA 93043
1	Naval Intelligence Command ATTN: NIPSSA-333 (Paul Fessler) 4600 Silver Hill Road Washington, DC 20389	1	Naval Postgraduate School Department of National Security ATTN: Dr. Joseph Sternberg Code 73 Monterey, CA 93943
1	Commander US Naval Ocean Systems Center ATTN: Earle G. Schweizer Code 000 San Diego, CA 92151-5000		

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Commander Intelligence Threat Analysis Center ATTN: PSD-GAS/John Bickle Washington Navy Yard Washington, DC 20374	1	USAF HQ ESD/PLEA Chief, Engineering and Test Division ATTN: Paul T. Courtoglous Hanscom AFB, MA 01730
1	Commander Intelligence Threat Analysis Center ATTN: Bill Davies Washington Navy Yard, Bldg 203 (Stop 314) Washington, DC 20374-2136	1	USAF-HQ ATTN: AFTDEC/JT (COL Victor A. Kindurys) Kirtland AFB, NM 87117-7001
1	Commander Intelligence Threat Analysis Center ATTN: Ron Demeter Washington Navy Yard, B-213, Stop 314 Washington, DC 20374	2	AFATL ATTN: AGA (Lawrence Jones) (Mickie Phipps) Eglin AFB, FL 32542-5434
1	Commander Intelligence Threat Analysis Center ATTN: Tim Finnegan Washington Navy Yard, B-213 Washington, DC 20374	1	AFEWC ATTN: AFEWC/SAXE (Bod Eddy) Kelly AFB, TX 78243-5000
1	Commander Intelligence Threat Analysis Center ATTN: Jim Fry Washington Navy Yard, B-213 Washington, DC 20374	1	AFWAL/AARF ATTN: CPT John Poachon Wright-Patterson AFB, OH 45433-6533
2	Commander Intelligence Threat Analysis Center Intell Image Prod Div ATTN: John Creighton Al Fuerst Washington Navy Yard, Bldg 213 (IAX-O-II) Washington, DC 20374	1	AFWAL/FIES ATTN: James Hodges Sr. Wright-Patterson AFB, OH 45433-6523
2	Commander David W. Taylor Naval Ship and Development Center ATTN: W. Conley J. Schot Bethesda, MD 20084	2	Commander AFWAL/MLTC ATTN: LT Robert Carringer Dave Judson Wright-Patterson AFB, OH 45433-6533
1	USAF HQ AD/ENL ATTN: Robert L. Stovall Eglin AFB, FL 32542	1	WRDC/AARA ATTN: Michael L. Bryant Wright-Patterson AFB, OH 45433
		1	FTD/SDMBA ATTN: Charles Darnell Wright-Patterson AFB, OH 45433
		1	FTD/SDMBU ATTN: Kevin Nelson Wright-Patterson AFB, OH 45433

# DISTRIBUTION LIST

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	FTD/SQDRA ATTN: Greg Koesters Wright-Patterson AFB, OH 45433-6508	1	Air Force Armament Laboratory ATTN: AFATL/DLY (James B. Flint) Eglin AFB, FL 32542-5000
1	FTD ATTN: Tom Reinhardt Wright-Patterson AFB, OH 45433	1	Commander US Army FSTC ATTN: AIAST-RA-SG1 (Dr. Steven Carter) 220 Seventh Avenue Charlottesville, VA 22901-5396
1	FTD/SCRS ATTN: Amy Fox Schalle Wright-Patterson AFB, OH 45433	5	Commander US Army FSTC ATTN: Greg Crawford Chip Grobmeyer David P. Lutz Suzanne Hall Charles Hutson 220 Seventh Avenue Charlottesville, VA 22901-5396
1	FTD/SDJEO ATTN: Robert Schalle Wright-Patterson AFB, OH 45433	1	Commander US Army FSTC/CA3 ATTN: Scott Mingledorff 220 Seventh Avenue Charlottesville, VA 22901-5396
1	FTD/SDAEA ATTN: Joe Sugrue Wright-Patterson AFB, OH 45433	1	Commander US Army FSTC (UK) ATTN: MAJ Nigel Williams 220 Seventh Avenue Charlottesville, VA 22901-5396
1	AFWAL/AARA ATTN: Vincent Velten Wright-Patterson AFB, OH 45433	6	Institute for Defense Analyses (IDA) ATTN: Mr. Irwin A. Kaufman Mr. Arthur O. Kresse Mr. Arthur Stein Dr. Lowell Tonnessen Mr. Benjamin W. Turner Ms. Sylvia L. Waller 1801 N. Beauregard Street Alexandria, VA 22311
1	FTD/SQDRA ATTN: Larry E. Wright Wright-Patterson AFB, OH 45433	1	Institute for Defense Analyses ATTN: Carl F. Kossack 1005 Athens Way Sun City, FL 33570
1	ASD/XRJ ATTN: Ed Mahen Wright-Patterson AFB, OH 45433		
1	AD/CZL ATTN: James M. Heard Eglin AFB, FL 32542-5000		
1	AD/ENY ATTN: Dr. Stewart W. Turner Director of Engineering Analysis Eglin AFB, FL 32542-5000		
2	AD/ENYW ATTN: 2LT Michael Ferguson Jim Richardson Eglin AFB, FL 32542-5000		



# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Department of Commerce National Bureau of Standards Manufacturing Systems Group ATTN: B. Smith Washington, DC 20234	1	Aluminum Company of America ATTN: Charles Wood Alcoa Technical Center Alcoa Center, PA 15069
1	AAI Corporation ATTN: H. W. Schuette PO Box 126 Hunt Valley, MD 21030-0126	1	ANSER ATTN: James W. McNulty 1215 Jefferson Davis Highway Arlington, VA 22202
1	ABEX Research Center ATTN: Dr. Michael J. Normandia 65 Valley Road Mahwah, NJ 07430	1	ARC C-500 ATTN: John H. Bucher Modena Road Coatesville, PA 19320
1	Adelman Associates ATTN: Herbert S. Weintraub 291 North Bernardo Avenue Mountain View, CA 94014-5205	1	Armament Systems, Inc. ATTN: Gerard Zeller P.O. Box 158 211 West Bel Air Avenue Aberdeen, MD 21001
2	Aero Corporation ATTN: David S. Eccles Gregg Snyder P.O. Box 92957, M4/913 Los Angeles, CA 90009	1	Armored Vehicle Technologies ATTN: Coda M. Edwards PO Box 2057 Warren, MI 48090
1	AFELM, The Rand Corporation ATTN: Library-D 1700 Main Street Santa Monica, CA 90406	1	Auburn University Electrical Engineering Department ATTN: Dr. Thomas Shumpert Auburn University, AL 36849
2	Air Force Wright Aeronautical Labs ATTN: CDJ, CPT Jost CDJ, Joseph Faison Wright-Patterson AFB, OH 45433-6523	1	A.W. Bayer and Associates ATTN: Albert W. Bayer, President Marina City Club 4333 Admiralty Way Marina del Rey, CA 90292-5469
1	Alliant Computer Company ATTN: David Micciche 1 Monarch Drive Littleton, MA 01460	1	Battelle Research Laboratory Columbus Division 505 King Avenue Columbus, Ohio 43201-2693
1	Alliston Gas Turbine Division of GM ATTN: Michael Swift PO Box 420, SC S22B Indianapolis, IN 46260-0420	1	Battelle Research Laboratory ATTN: Bernard J. Tullington 1300 N. 17th Street, Suite 1520 Arlington, VA 22209

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	The BDM Corporation ATTN: Edwin J. Dorchak 7915 Jones Branch Drive McLean, VA 22102-3396	1	Booz Allen and Hamilton, Inc. ATTN: Lee F. Mallett 1300 N. 17th Street, Suite 1610 Rosslyn, VA 22209
1	The BDM Corporation ATTN: Fred J. Michel 1300 N. 17th Street Arlington, VA 22209	1	Booz-Allen and Hamilton, Inc. ATTN: John M. Vice AFWAL/FIES/SURVIAC Bldg 45, Area B Wright-Patterson AFB, OH 45433-6553
2	BMY, Division of Harsco ATTN: William J. Wagner, Jr. Ronald W. Jenkins PO Box 1512 York, PA 17404	1	John Brown Associates ATTN: Dr. John A. Brown PO Box 145 Berkeley Heights, NJ 07922-0145
1	Board on Army Science and Technology National Research Council Room MH 280 2101 Constitution Avenue, NW Washington, DC 20418	1	Chamberlain ATTN: Mark A. Sackett PO Box 2545 Waterloo, IA 50704
2	Boeing Aerospace ATTN: Dr. Robert Chiavetta Dr. John Kuras Mail Stop 8K17 P.O. Box 3999 Seattle, WA 98124-2499	1	Combined Arms Combat Development ATTN: ATZL-CAP (LTC Morrison) Dir, Surv Task Force Ft. Leavenworth, KS 66027-5300
2	Boeing Corporation ATTN: MS 33-04, Robert Bristow MS 48-88, Wayne Hammond PO Box 3707 Seattle, WA 98124-2207	1	Computer Sciences Corporation 200 Sparkman Drive Huntsville, AL 35805
1	Boeing Vertol Company A Division of Boeing Co. ATTN: MS P30-27, John E. Lyons PO Box 16858 Philadelphia, PA 19142	3	Computervision Corporation ATTN: A. Bhide V. Geisberg R. Hillyard 201 Burlington Road Bedford, MA 01730
1	Booz-Allen and Hamilton, Inc. ATTN: Dr. Richard B. Benjamin Suite 131, 4141 Colonel Glenn Hwy. Dayton, OH 45431	1	Cray Research, Inc. ATTN: William W. Kritlow 2130 Main Street, #280 Huntington Beach, CA 92648
		1	CRS Serrine, Inc. ATTN: Dr. James C. Smith PO Box 22427 1177 West Loop South Houston, TX 77227

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	CSC ATTN: Abner W. Lee 200 Sparkman Drive Huntsville, AL 35895	1	DuPont Company FPD ATTN: Dr. Oswald R. Bergmann B-1246, 1007 Market Street Wilmington, DE 19898
2	Cypress International ATTN: August J. Caponecchi James Logan 1201 E. Abinjdou Drive Alexandria, VA 22314	1	Dynamics Analysis and Test Associates ATTN: Dr. C. Thomas Savell 2231 Faraday Ave Suite 103 Carlsbad, CA 92008
1	DATA Networks, Inc. ATTN: William E. Regan, Jr. President 288 Greenspring Station Brooklandville, MD 21022	1	E. I. Dupont TED FMC ATTN: Richard O. Myers Jr. Wilmington, DE 19898
1	Datatec, Inc. ATTN: Donald E. Cudney President 326 Green Acres Fort Walton, FL 32548	1	Eichelberger Consulting Company ATTN: Dr. Robert Eichelberger President 409 West Catherine Street Bel Air, MD 21014
1	University of Dayton Graduate Engineering and Research Kettering Lab 262 ATTN: Dr. Gary Thiele, Director Dayton, OH 45469	1	Electronic Warfare Associates, Inc. ATTN: William V. Chiaramonte 2071 Chain Bridge Road Vienna, VA 22180
1	Delco Systems Operation ATTN: John Steen 6767 Hollister Avenue, #P202 Goleta, CA 93117	1	Emprise, Ltd. ATTN: Bradshaw Armendt, Jr 201 Crafton Road Bel Air, MD 21014
1	Denver Research Institute Target Vulnerability and Survivability Laboratory ATTN: Lawrence G. Ulliyatt PO Box 10127 Denver, CO 80210	8	Environmental Research Institute of Michigan ATTN: Mr. K. Augustyn Mr. Kozma Dr. I. La Haie Mr. R. Horvath Mr. Arnold Mr. E. Cobb Mr. B. Morey Mr. M. Bair PO Box 8618 Ann Arbor, MI 48107
1	Denver Research Institute University of Denver ATTN: Louis E. Smith University Park Denver, CO 80208	1	E-OIR Measurements, Inc. ATTN: Russ Moulton PO Box 3348, College Station Fredericksburg, VA 22402

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	John Fluke Manufacturing Company, Inc. ATTN: D. Gunderson PO Box C9090 Everett, WA 98206	7	FMC Corporation Ordnance Engineering Division ATTN: H. Croft M. Hatcher L. House J. Jackson M. Krull E. Maddox R. Musante 1105 Coleman Ave, Box 1201 San Jose, CA 95108
3	FMC Corporation ATTN: Ronald S. Beck Martin Lim Jacob F. Yacoub 881 Martin Avenue Santa Clara, CA 95052	1	GE Aircraft Engines ATTN: Dr. Roger B. Dunn One Neumann Way, MD J185 Cincinnati, OH 45215-6301
3	FMC Corporation Advanced Systems Center (ASC) ATTN: Edward Berry Scott L. Langlie Herb Theumer 1300 South Second Street PO Box 59043 Minneapolis, MN 55459	1	General Atomics ATTN: Chester J. Everline, Staff Engineer P.O. Box 85608 San Diego, CA 92138-5608
2	FMC Corporation Defense Systems Group ATTN: Robert Burt Dennis R. Nitschke 1115 Coleman Avenue San Jose, CA 95037	1	General Dynamics ATTN: Dr. Fred Cleveland P.O. Box 748 Mail Zone 5965 Ft. Worth, TX 76101
1	FMC Corporation Naval Systems Division (NSD) ATTN: MK-45, Randall Ellis Minneapolis, MN 55421	3	General Dynamics ATTN: MZ-4362112, Robert Carter MZ-4362029, Jim Graciano MZ-4362055, Gary Jackman 38500 Mound Sterling Heights, MI 48310
1	FMC Corporation Northern Ordnance Division ATTN: M3-11, Barry Brown 4800 East River Road Minneapolis, MN 55421	1	General Dynamics Data Systems Services ATTN: R. Fridshal PO Box 80847 San Diego, CA 92138
		1	General Dynamics ATTN: Jay Lobb 1055 Maple Road Clawson, MI 48017

# DISTRIBUTION LIST

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
3	General Dynamics Corporation ATTN: MZ-2650, Dave Bergman MZ-2860, John Romanko MZ-2844, Cynthia Waters PO Box 748 Ft. Worth, TX 76101-0748	1	Honeywell ATTN: Fred J. Parduhn 7225 Northland Drive Brooklyn Park, MN 55428
1	General Dynamics Land Systems ATTN: Dr. Paulus Kersten PO Box 1901 Warren, MI 48090	2	Honeywell, Inc. ATTN: Raymond H. Burg Laura C. Dillway MN38-4000 10400 Yellow Circle Drive Minnetonka, MN 55343
1	General Dynamics Land Systems ATTN: William M. Mrdeza PO Box 2045 Warren, MI 48090	2	INEL/EGandG Engineer Lab ATTN: Ray Berry M. Marx Hintze PO Box 1625 Idaho Falls, ID 83451
3	General Dynamics Land Systems ATTN: Richard Auyer Otto Renius N. S. Sridharan PO Box 2074 Warren, MI 48090	1	Interactive Computer Graphics Center Rensselaer Polytechnic Inst. ATTN: M. Wozny Troy, NY 12181
3	General Motors Corporation Research Laboratories ATTN: J. Boyse J. Joyce R. Sarraga Warren, MI 48090	1	International Development Corporation ATTN: Trevor O. Jones 18400 Shelburne Road Shaker Heights, OH 44118
1	Gettysburg College Box 405 Gettysburg, PA 17325	1	ISAT ATTN: Roderick Briggs 1305 Duke Street Alexandria, VA 22314
1	Grumman Aerospace Corporation Research and Development Center ATTN: Dr. Robert T. Brown, Senior Research Scientist Bethpage, NY 11714	1	Jet Propulsion Laboratory California Institute of Technology ATTN: D. Lewis 4800 Oak Grove Drive Pasadena, CA 91109
1	GTRI-RAIL-MAD ATTN: Mr. Joe Bradley CRB 577 Atlanta, GA 30332	1	Kaman Sciences Corporation ATTN: Timothy S. Pendergrass 600 Boulevard South, Suite 208 Huntsville, AL 35802

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Ketron, Inc. ATTN: Robert S. Bennett 696 Fairmont Avenue Towsontown Center Towson, MD 21204	1	Logistics Management Institute ATTN: Edward D. Simms Jr. 6400 Goldsboro Road Bethesda, MD 20817-5886
1	Keweenaw Research Center Michigan Technological University ATTN: Bill Reynolds Houghton, MI 49931	1	Los Alamos Technical Associates, Inc. ATTN: John S. Daly 6501 Americas Parkway, #900 Albuquerque, NM 87110
1	Lanxido Armor Products ATTN: Dr. Robert A. Wolffe Tralee Industrial Park Newark, DE 19711	1	LTV ATTN: MS 194-51, Mike Logan PO Box 225907 Dallas, TX 75265
2	Lincoln Laboratory MIT ATTN: Dr. Robert Shin Dr. Chuck Burt P.O. Box 73 Lexington, MA 02173	1	LTV Aerospace and Defense ATTN: Daniel M. Reedy PO Box 225907 Dallas, TX 75265
3	Lincoln Laboratory MIT Surveillance Systems Group ATTN: R. Barnes G. Knittel J. Kong 244 Wood Street Lexington, MA 02173-0073	2	Martin Marietta Aerospace ATTN: MP-113, Dan Dorfman MP-433, Richard S. Dowd PO Box 5837 Orlando, FL 32855-5837
1	Lockheed Corporation ATTN: R. C. Smith PO Box 551 Burlank, CA 91520	3	Mathematical Applications Group, Inc. ATTN: M. Cohen R. Goldstein H. Steinberg 3 Westchester Plaza Elmsford, NY 10523
3	Lockheed-California Company ATTN: C. A. Burton R. J. Ricci M. Steinberg Burbank, CA 91520	1	Maxwell Laboratories, Inc. ATTN: Dr. Michael Holland 8888 Balboa Avenue San Diego, CA 92123-1506
2	Lockheed-Georgia Company ATTN: Ottis F. Teuton J. Tulkoff Dept. 72-91, Zone 419 Marietta, GA 30063	1	McDonald-Douglas Astronautic ATTN: Nikolai A. Louie 5301 Bolsa Avenue Huntington Beach, CA 92647
		1	McDonnell Douglas, Inc. ATTN: David Hamilton PO Box 516 St. Louis, MO 63166

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	McDonnell Douglas, Inc. ATTN: Alan R. Parker 3855 Lakewood Blvd., MC 35-18 Long Beach, CA 90846	1	NAVIR DEVCON ATTN: Frank Wenograd Code 6043 Walminstor, PA 18974
1	McLean Research Center, Inc. ATTN: Robert D. Carpenter 1483 Chain Bridge Road, Suite 205 McLean, VA 22101	1	North Aircraft ATTN: Dr. Athanos Varvatsis Mail Zone 3622/84 1 Northrop Ave Hawthorne, CA 90250
1	Megatek Corporation United Telecom Computer Group ATTN: J. Phrohaska 7700 Leesburg Pike, Suite 106 Falls Church, VA 22043	1	Northrop Corporation Electro-Mechanical Division ATTN: Engh R. Byron 500 E. Orangethorpe Ave., 7270 Anaheim, CA 92801
1	Memex Corporation ATTN: Charles S. Smith 91 Belleau Ave. Atherton, CA 94025	1	Northrop Corporation Research and Technology Center ATTN: James R. Reis One Research Park Palos Verdes Peninsula, CA 90274
1	Micro Electronics of North Carolina ATTN: Gershon Kedem PO Box 12889 Research Triangle Park, NC 07709	1	Norton Company ATTN: Ronald K. Bart 1 New Bond Street Worcester, MA 01606-2698
1	MIT ATTN: Dr. S. Benton RE15-416 Cambridge, MA 02139	1	The Oceanus Company ATTN: RADM Robert H. Gormley, (Ret) PO Box 7069 Menlo Park, CA 94026
1	The MITRE Corporation ATTN: Edward C. Brady, Vice President 7525 Colshire Drive McLean, VA 22102	1	Okalahoma State University College of Engineering, Architecture and Technology ATTN: Thomas M. Browder, Jr. PO Box 1925 Eglin AFB, FL 32542
1	NASA-Ames Research Center ATTN: Dr. Alex Woo Mail Stop 227-2 Moffett Field, CA 94035	1	Pacific Scientific/Htl Division ATTN: Robert F. Aldrich 1800 Highland Avenue Duarte, CA 91010
1	NASA-Ames Research Center ATTN: Leroy Presley Mail stop 227-4 Moffett Field, CA 94035		

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Perceptronics, Inc. ATTN: Dean R. Loftin 21111 Erwin Street Woodland Hills, CA 91367	1	Sachs/Freeman Associates, Inc. ATTN: Donald W. Lynch Senior Research Physicist 205 Yoakum Parkway, #511 Alexandria, VA 22304
1	Physics International ATTN: Ron Gellatly 2700 Merced Street San Leandro, CA 94577	1	SAIC ATTN: Dr. Alan J. Toepfer 2109 Air Park Drive, SE Albuquerque, NM 87106
1	PRI, Inc. ATTN: W. Bushell Building E4435, Second Floor Edgewood Area-APG, MD 21010	1	SAIC ATTN: John H. McNeilly, Senior Scientist 1710 Goodridge Drive McLean, VA 22102
1	RGB Associates, Inc. ATTN: R. Barakat Box B Wayland, MA 01778	2	SAIC ATTN: Terry Keller Robert Turner Suite 200 1010 Woodman Drive Dayton, OH 45432
1	Rockwell International ATTN: Dr. H. Bran Tran P.O. Box 92098 Department 113/GB01 Los Angeles, CA 90009	1	SAIC ATTN: David R. Garfinkle Malibu Canyon Business Park 26679 W. Agoura Road, Suite 200 Calabasas, CA 91302
1	Rockwell International Corporation ATTN: Keith R. Rathjen, Vice President 3370 Miraloma Avenue (031-HA01) Anaheim, CA 92803-3105	1	Sidwell-Ross and Associates, Inc. ATTN: LTG Marion C. Ross, (USA Ret) Executive Vice President PO Box 88531 Atlanta, GA 30338
1	Rome Air Development Center ATTN: RADC/IRRE, Peter J. Costianes Griffis Air Force Base, NY 13441-5700	1	Sigma Research Inc. ATTN: Dr. Richard Bossi 8710 148 Avenue, NE Redmond, WA 98052
1	Rome Air Development Center RADC/OCTM ATTN: Edward Starczewski Building 106 Griffis Air Force Base, NY 13441-5700	1	Sikorsky Aircraft Division of United Technologies ATTN: R. Welge North Main Street Stratford, CT 06602
1	S-Cubed ATTN: Michael S. Lancaster 1800 Diagonal Road, Suite 420 Alexandria, VA 22314		



# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Simula, Inc. ATTN: Joseph W. Coltman 10016 South 51st Street Pheonix, AZ 85044	2	TASC ATTN: Charles E. Clucus Darrell James 970 Mar-Walt Drive Ft. Walton Beach, FL 32548
1	Alan Smolen and Associates, Inc. ATTN: Alan Smolen, President One Cynthia Court Palm Coast, FL 32027-8172	1	TASC ATTN: Harry I. Nimon, Jr 1700 N. Moore Street, Suite 1220 Arlington, VA 22209
3	Southwest Research Institute ATTN: Martin Goland Alex B. Wenzel Patrick H. Zabel 6220 Culebra Road San Antonio, TX 78238	1	Technical Solutions, Inc ATTN: John R. Robbins P.O. Box 1148 Mesillia Park, NM 88047
3	Sparta, Inc. ATTN: David M. McKinley Robert E. O'Connor Karen M. Rooney 4901 Corporate Drive Huntsville, AL 35805-6201	1	Tradeways, Ltd. ATTN: Joseph G. Gorski, President 307F Maple Avenue West Vienna, VA 22180
3	Structural Dynamics Research Corporation (SDRC) ATTN: R. Ard W. McClelland J. Osborn 2000 Eastman Drive Milford, NH 45150	2	TRW Operations and Support Group ATTN: K. Dankers T. Heim One Space Park Redondo Beach, CA 90278
1	Syracuse Research Group ATTN: Dr. Chung-Chi Cha Merrill Lane Syracuse, NY 13210	1	United Technologies Corporation Advanced Systems Division ATTN: Richard J. Holman 10180 Telesis Court San Diego, CA 92121
1	System Planning Corporation ATTN: Ann Hafer 1500 Wilson Blvd Arlington, VA 22209	1	United Technologies Research Center ATTN: Dr. Brian J. McCartin Senior Research Mathematician East Hartford, CT 06108
1	Systems Science and Software ATTN: Robert T. Sedgwick PO Box 1620 La Jolla, CA 92038-1620	1	University of Idaho Department of Civil Engineering ATTN: Dr. Dennis R. Horn Assistant Professor Moscow, ID 83843-4194

# DISTRIBUTION LIST

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	University of Illinois at Urbana-Champaign Department of Civil Engineering and Environmental Studies ATTN: Dr. E. Downey Brill, Jr. 208 North Remine Urbana, IL 61801-2374	2	University of Washington 409 Department of Electrical Engineering, FT-10 ATTN: Dr. Irene Peden Dr. Akira Ishimaru Seattle, WA 98105
1	University of Illinois Department of Electrical and Computer Engineering ATTN: Dr. Shung-Wu Lee 1406 W. Green Urbana, IL 61801	1	Van Es Associates, Inc. ATTN: Dr. John D. Christie Vice President Suite 1407, 5202 Leesburg Pike Falls Church, VA 22041
1	The Johns Hopkins University Applied Physics Laboratory ATTN: Jonathan Fluss Johns Hopkins Road Laurel, MD 20707	1	Virginia Polytechnic Institute and State University Industrial Engineering Operations Research Department ATTN: Robert C. Williges 302 Whittemore Hall Blacksburg, VA 24061-8603
1	University of Nevada Environmental Research Center ATTN: Dr. Delbert S. Barth Senior Scientist Las Vegas, NV 89154-0001	1	Vought Corporation ATTN: Paul T. Chan PO Box 225907 Dallas, TX 75265
1	University of North Carolina ATTN: Professor Henry Fuchs 208 New West Hall (035A) Chapel Hill, NC 27514	1	XMCO, Inc. ATTN: LTG Robert J. Baer, (USA Ret), Senior Vice President 11150 Sunrise Valley Drive Reston, VA 22091-4399
3	Ohio State University Electroscience Laboratory ATTN: Dr. Ronald Marhefka Dr. Edward H. Newman Dr. Prasbhaker H. Pathak 1320 Kinnear Road Columbus, OH 43212	1	XONTECH ATTN: John Dagostino 1701 N. Fort Myer Drive Suite 703 Arlington, VA 22209
3	University of Utah Computer Science Department ATTN: R. Riesenfeld E. Cohen L. Knapp 3160 Merrill Engineering Bldg Salt Lake City, UT 84112	1	Zernow Tech Services, Inc. ATTN: Dr. Louis Zernow 425 West Bonita, Suite 208 San Dimas, CA 91773
		2	SURVICE Engineering ATTN: Jim Foulk George Lard 1003 Old Philadelphia Road Aberdeen, MD 21001

# DISTRIBUTION LIST

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Georgia Technical Research Institute Systems and Technical Laboratory ATTN: Dr. Charles Watt 1770 Richardsons Road Smyrna, GA 30080	1	Dr. Edward R. Jones, Private Consultant 9881 Wild Deer Road St. Louis, MO 63124
1	Duke University Department of Computer Science, VLSI Raycasting ATTN: Dr. Gershon Kedem 236 North Building Durham, NC 27706	1	MG Robert Kirwan (USA Ret) 10213 Grovewood Way Fairfax, VA 22032
1	Dr. Robert E. Ball 642 Tyon Drive Monterey, CA 93940	1	Donald J. Krejcarek US Army Field Artillery Board 4717 NE Macarthur Circle Lawton, OK 73511
1	Mr. Michael W. Bernhardt Rt. 1, 12 Arthur Drive Hockessin, DE 19707	1	Mr. Robert B. Kurtz, Private Consultant 542 Merwins Lane Fairfield, CT 06430-1920
1	Mr. H. G. Bowen Jr. 408 Crown View Drive Alexandria, VA 22314-4804	1	Dr. Roy A. Lucht Group M-B MS-J960 Los Alamos, NM 87545
1	Mr. Harvey E. Cale 2561 Meadowbrook Lane Carson City, NV 89701-5726	1	Mr. Donald F. Menne 617 Foxcroft Drive Bel Air, MD 21014
1	Mr. Robert L. Deitz Perkins Coie 1110 Vermont Avenue, NW Suite 200 Washington, DC 20005	1	MG Peter G. Olenchuk (USA Ret) 6801 Baron Road McLean, VA 22101
1	Thomas Hafer 1500 Wilson Blvd. 14th Floor Arlington, VA 22209	1	Mr. Albert E. Papazoni 1600 Surrey Hill Drive Austin, TX 78746-7338
1	Mr. William M. Hubbard, Consultant 613 Eastlake Drive Columbia, MO 65203	1	Dr. A. E. Schmidlin 28 Highview Road Caldwell, NJ 07006-5502
1	Mr. Charles E. Joachim PO Box 631 Vicksburg, MS 39180	1	Mr. Arthur Stein, Consultant 30 Chapel Woods Court Williamsville, NY 14221-1816
		1	Dr. Dora Strother 3616 Landy Lane Ft. Worth, TX 76118

DISTRIBUTION LIST

Aberdeen Proving Ground

Dir, USAMSAA

ATTN: AMXSY-A, W. Clifford  
J. Meredith

AMXSY-C, A. Reid

AMXSY-CR, M. Miller

AMXSY-CS, P. Beavers  
C. Cairns

D. Frederick

AMXSY-G, J. Kramer

AMXSY-GA, W. Brooks

AMXSY-J, A. LaGrange

AMXSY-L, J. McCarthy

AMXSY-RA, R. Scungio  
M. Smith

Cdr, USATECOM

ATTN: AMSTE-CG, C. Drenz

AMSTE-LFT, D. Gross  
R. Harrington

## USER EVALUATION SHEET/CHANGE OF ADDRESS

This Laboratory undertakes a continuing effort to improve the quality of the reports it publishes. Your comments/answers to the items/questions below will aid us in our efforts.

1. BRL Report Number BRL-MR-3815 Date of Report MARCH 1990
2. Date Report Received \_\_\_\_\_
3. Does this report satisfy a need? (Comment on purpose, related project, or other area of interest for which the report will be used.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
4. Specifically, how is the report being used? (Information source, design data, procedure, source of ideas, etc.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
5. Has the information in this report led to any quantitative savings as far as man-hours or dollars saved, operating costs avoided, or efficiencies achieved, etc? If so, please elaborate. \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
6. General Comments. What do you think should be changed to improve future reports? (Indicate changes to organization, technical content, format, etc.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

### CURRENT ADDRESS

\_\_\_\_\_  
Name

\_\_\_\_\_  
Organization

\_\_\_\_\_  
Address

\_\_\_\_\_  
City, State, Zip Code

### OLD ADDRESS

\_\_\_\_\_  
Name

\_\_\_\_\_  
Organization

\_\_\_\_\_  
Address

\_\_\_\_\_  
City, State, Zip Code

7. If indicating a Change of Address or Address Correction, please provide the New or Correct Address in Block 6 above and the Old or Incorrect address below.

(Remove this sheet, fold as indicated. staple or tape closed, and mail.)

-----FOLD HERE-----

**DEPARTMENT OF THE ARMY**

Director  
U.S. Army Ballistic Research Laboratory  
ATTN: SLCBR-DD-T  
Aberdeen Proving Ground, MD 21005-5066  
**OFFICIAL BUSINESS**



**NO POSTAGE  
NECESSARY  
IF MAILED  
IN THE  
UNITED STATES**

**BUSINESS REPLY MAIL**  
FIRST CLASS PERMIT No 0001, APG, MD

POSTAGE WILL BE PAID BY ADDRESSEE

Director  
U.S. Army Ballistic Research Laboratory  
ATTN: SLCBR-DD-T  
Aberdeen Proving Ground, MD 21005-9989

-----FOLD HERE-----